

























This report was prepared by the NWRM project, led by Office International de l'Eau (OIEau), in consortium with Actéon Environment (France), AMEC Foster Wheeler (United Kingdom), BEF (Baltic States), ENVECO (Sweden), IACO (Cyprus/Greece), IMDEA Water (Spain), REC (Hungary/Central & Eastern Europe), REKK inc. (Hungary), SLU (Sweden) and SRUC (UK) under contract 07.0330/2013/659147/SER/ENV.C1 for the Directorate-General for Environment of the European Commission. The information and views set out in this report represent NWRM project's views on the subject matter and do not necessarily reflect the official opinion of the Commission. The Commission does not guarantee the accuracy of the data included in this report. Neither the Commission nor any person acting on the Commission's behalf may be held Key words: Biophysical impact, runoff, water retention, effectiveness - Please consult the NWRM glossary for more information.

NWRM project publications are available at http://www.nwrm.eu

Table of content

I.	Basic Information	. 1
II.	Policy context and design targets	. 2
III.	Site characteristics	. 2
IV.	Design & implementation parameters	. 3
V.	Biophysical impacts	. 5
VI.	Socio-Economic Information	. 6
VII.	Monitoring & maintenance requirements	. 8
VIII	. Performance metrics and assessment criteria	. 8
IX.	Main risks, implications, enabling factors and preconditions	. 9
X.	Lessons learned	. 9
XI.	References	. 9
XII.	Photos Gallery	10

I. <u>Basic Information</u>

Application ID	Greece_01			
(Country_Numeric, e.g.: Greece_01)				
Application Name	Water retention management in the broader area of Ancient Olympia, Elia,			
(provide a short name)	Greece			
Application Location	Country:	Greece	Country 2:	
	(select from list in		In case of transboundary	
	Annex 1)		applications	
	NUTS2 Code (selec	et from list in	EL23	
	Annex 1)	_		
	River Basin Distric	t Code <i>(select</i>	GR01	
	from list in Annex 1)			
	WFD Water Body	Code (select	GR0129R000215044H (Alpheos	
	from list in Annex 1)		Water Body)	
	Description		The study area is located in Ancient	
	(free text, short descr	ription of the	Olympia, Elia, Peloponnese, Greece.	
	location)			
Application Site Coordinates	Latitude:		Longitude:	
(in ETRS89 or WGS84 the	37,3835085 (φ)		21,378061 (λ)	
coordinate system)				
Target Sector(s)	Primary:	Forest		
Implemented NWRM(s)	Measure #1:	Afforestatio	on of mountain areas (F2)	
Application short description	Measure #1: Afforestation of mountain areas (F2) The measures include the temporary installation of structures utilizing locally available timber in order to increase water retention. The installation of the timber structures has been fixed parallel to the contours of the hills slopes in order to retain water. They were constructed from the cutting trunks of burned Aleppo Pine (Pinus helepensis) and Cypress (Supressus semprervirens) and they were secured on wooden stakes without any metal supports. This construction method was selected to avoid major landscape intervention and to preserve the ecological balance of the ecosystem. Their distances were determined according to log characteristics and also to topographic and hydro-meteorological conditions of each site they secure. They were also placed in a "mosaic design" consisting from single or double in high logs according to the gradient of the slopes. Additionally, the occurrence of soil erosion and overland flow contributed to severe flooding problems. These measures retained a total of 7.5 mm of fertile soil and the total soil material that was retained is estimated about 2.500 m3/30 ha. The flood events mainly affected the archaeological sites and the surrounding areas. An additional intervention refers to targeted planting of forests in mountain areas that can help stabilize hill slopes, thereby reduce erosion and potentially leading to greater water retention in the mountain areas. Afforestation may have beneficial impact on the hydrograph by reducing peak flows and enabling the maintenance of base flows. The potential for water retention must be balanced against the increased ET and pollutant trapping that may be associated with forests.			

II. Policy context and design targets

Brief description of the problem to be tackled	The specific interventions aim at tackling the environmental impacts of the significant wildfires of the study area in 2007. The principal aim of the works includes reduction of soil erosion and flood management. The interventions also include burned trees harvesting and restoration actions on the existing vegetation and on the tree crops.			
What were the primary & secondary targets when	Primary target #1:	Flood control and flood risk	c mitigation	
designing this application?	Primary target #2:	Mass stabilisation and cont	rol of erosion rates	
	Secondary target #1:	Biodiversity and gene-pool areas	conservation in riparian	
	Remarks	The primary targets when des soil erosion management, flo mitigation in the context of res	od control and flood risk	
Which specific types of pressures did you aim at mitigating?	Pressure #1:	Floods Directive indetified pressure	Other pressure contributing to flooding / flood risk	
	Pressure #2:	WFD indentified pressure	Other hydromorphological alterations	
	Remarks			
Which specific types of adverse impacts did you aim at	Impact #1:	Floods Directive indetified impact	Other Environmental impacts	
mitigating?	Impact #2:	WFD indentified impact	Altered habitats due to hydrological changes	
	Remarks			
Which EU requirements and EU Directives were aimed at being addressed?	Requirement #1:	Floods Directive- mitigating Flood Risk	Flood risk management and flood impacts mitigation	
	Requirement #2:	WFD-mitigation of significant pressure	Mitigation of hydromorphological alterations e.g. soil erosion	
	Remarks			
Which national and/or regional policy challenges and/or requirements aimed to be addressed?	Law 3199/2003 & Presidential Decree (P.D.) No. 51/2007 (protection of water resources)			

III. Site characteristics

Dominant Land Use type(s)	Dominant land use	313	
Select from the drop-down menu	Secondary land use	211	
with the CORINE LU types and	Other important land use		
codes.	The land use has changed from forests and other wooded land to arable land.		
Climate zone	warm temperate moist		

Soil type	Luvisols	
Average Slope	very steep (>60%)	
Mean Annual Rainfall	300 - 900 mm	
Mean Annual Runoff	600 - 750 mm	
Average Runoff coefficient (or % imperviousness on site)	The measures to prevent soil erosion and flood events have positive impact on the reduction of runoff and the increase of vegetation in the burned area.	
Characterization of water quality status (prior to the implementation of the NWRMs)	Prior to the NWs and after the wildfires the water quality was poor. Regarding groundwater quality, due to decreased water retention, the rainwater did not infiltrate the soil and did not enrich the aquifers. As far as surface water is concerned, the wildfires have deteriorated the vegetation quality; thus the quality of water runoff was decreased. Please link to the WFD water quality parameters (nutrients N,P; organic pollution; chemical pollution, Cu, Zn; saline pollution; TSS; acidification, elevated temperatures; E.coli, Fecal coliforms, etc.)	
Comment on any specific site characteristic that influences the effectiveness of the applied NWRM(s) in a positive or negative way		

IV. <u>Design & implementation parameters</u>

Project scale	Medium (eg. public park, new development district)	It is a medium scale project as it involves the 4 hills around the Ancient Olympia	
	Date of installation/construction	The installation / construction period was planned between 11/2007 and 02/2008.	
Time frame	Expected average lifespan (life expectancy) of the application in years	The designed lifespan of the application NWRM is 4-5 years as after this time the vegetation itself will take over the erosion and flood risk.	
	Name of responsible authority/ stakeholder	Role, responsibilities	
	1. Hellenic Ministry of Culture and Sports	Beneficiary	
Responsible authority and other stakeholders involved	2. Z' Ephorate of Prehistoric and Classical Antiquities.	Responsible for monitoring the work progress	
other stakeholders hivolved	3. Institute of Mediterranean and Forest Ecosystems	Scientific responsible	
	4. Forest Products Technology of the National Agricultural Research Foundation (NAGREF)	Scientific responsible	
	5.		
The application was initiated and financed by The application was initiated and financed by The application was initiated by the Institute of Mediterran Ecosystems and Forest Products Technology of the Nation (NAGREF) and funded by donations Public Benefit Foundation.		echnology of the National Agricultural	

What were specific principles that were followed in the design of this application?	The specific principles that were followed in the design of this application include aesthetic benefit, functionality, integrative planning, impact on public perception & acceptability, etc.		
	Number of hectares treated NWRM(s).	d by the	49.5
Area (ha)	49.5 ha are the area affected by the Hill, International Olympic Acade. Academy – Zone B, Zouni Hill, Kolo In these areas 80-100% of the vegetati	my – Zone 2 saka Hill.	A, International Olympic
Design capacity	The temporary structures utilizing locally available timber have been designed to reduce the hill slopes thus attenuate the surface runoff as well as the sentiment volume. This measure enables the increase of soil moisture, water absorption, and infiltration. Additionally, it creates suitable sites for natural regeneration or technical afforestation of the burned area. The maximum volume of runoff water that can be retained has not been assessed as this was not originally a water retention application but the restoration of the surrounding of the archaeological site		
	Reference		URL
Reference to existing engineering standards,	1.	Non available information	Non available information
guidelines and manuals that	2.		
have been used during the design phase	3.		
design phase	4.		
	5.		
Main factors and/or constraints that influenced the selection and design of the NWRM(s) in this application?	by the combustion of organic matterwhich increases surface runoff and flood risk. The local climate, with an annual procipitation of over 1,000 mm and often		

V. <u>Biophysical impacts</u>

Impact category	Impact description (Text, approx. 200 words)	Impact (specifying unit	quantification
(short name)		Parameter	% change in
		value; units	parameter value
Select from the		varae, arres	as compared to
drop-down			the state prior
menu below:			to the
			implementation
*			of the
			NWRM(s)
Runoff	The installation of temporary structures utilizing locally		111111(0)
attenuation /	available timber have been designed to reduce the hill slopes		
control	thus control the surface runoff. This measures reduces the		
Control	velocity of water volume leading to decreasing the intensity and		
	frequency of floods. Also the timber structures retain water for		
	longer period enabling the infiltration/percolation and recharge		
	of aquifers.		
	The peak flow rate is reduced due to the obstacle of the timber		
Peak flow rate	structures. This measures reduces the velocity of water volume		
reduction	resulting in the decrease of floods intensity.		
	These measures have an impact on the increase of the		
	groundwater level due to the increased infiltration, percolation		
Impact on	and recharge that is achieved through the slowing down of		
groundwater	water velocity. Also vegetation succeeded in eliminating the		
groundwater	hydrophobic layer that was created in the soil after the fires		
	and enables the water absorption towards the aquifers.		
	These measures have a direct impact on soil moisture as the	The rating fo	r hydro-seeding
Impact on soil	temporary timber structures enable to retain water for a longer	was 60% "exce	
moisture and	period and inhibit the volume of runoff. Additionally, the area		the log erosion
soil storage	afforestation succeeds in eliminating the hydrophobic layer that	barriers was	U
capacity	was created in the soil after the fires and thus increased soil	"good" in	70% of the
capacity	storage capacity.	measurements.	70,0 01 010
Restoring	www.g. wp.m.y.		
hydraulic			
connection			
Water quality			
Improvements			
*	These measures have an impact on the ecological status of the		
WFD	water bodies of the specific river basin as they improve the		
Ecological	quality of the surface water (improved water quality standards		
Status and	due to vegetation) and the quality and quantity of the		
objectives	groundwater (increased soil infiltration)		
D 1 : 2 1	These measures reduce the flood risks as the timber structures		
Reducing flood	function as a water retainer that slows down the velocity of		
risks (Floods	water volume thus the surface runoff resulting in the decrease of		
Directive)	floods frequency and intensity.		
Mitigation of			
other			
biophysical			
1 /			

impacts in		
relation to		
other EU		
Directives (e.g.		
Habitats,		
UWWT, etc.)		
Soil Quality Improvements	These measures have a direct impact on the overall soil quality as afforestation of the area succeeds in eliminating the hydrophobic layer that was created in the soil after the fires and thus increase soil storage capacity. The fires have created the porosity of the soil to decrease, thus the restoration has positive impact on the soil infiltration capacity. Also the soil is improved due to the increase of the moisture.	ated soil material ntion of a total 7.5
Other		

VI. <u>Socio-Economic Information</u>

What are the benefits and co-benefits of NWRMs in this application?	The direct benefits include the reduction of the flood risk, the improvement of the micro-environment as well as the aesthetic restoration of the affected area. Additional indirect benefits of the measures in this application include the increase of groundwater quantity of the river basin in order to be used for different uses as well as for ecosystem services.			
	Total:	2,762,500 €	In terms of breakdown, the cost for the log barriers is not assessed in the provided information.	
	Capital:	Value in €	The irrigation system for the four hills was $464.658 \in \text{plus}$ VAT .	
Financial costs	Land acquisition and value:	1,500,000 €	The cost for land compensations was about 1.500.000 € due to the overpriced value of the properties around the archeological site.	
	Operational:	Value in €	The operational cost for irrigation as well as for pruning and fertilizer application was not assessed.	
	Maintenance:	Value in €		
	Other:	Value in €		
	Was financial compensation required: Yes			
	Total amount of money paid (in €): 1,500,000			
Were financial compensations required? What amount?	Compensation schema: The financial compensations were for 5-6 beneficiaries-fields with a total area of 10 hectares each.			
White amount.	Comments / Remarks: The cost per hectare for this high value area was about 20,000-30,000 ϵ ; thus the total cost for land			
	compensations was	s about 1,000,00	0 €.	

Economic costs	Actual income loss: The actual income loss for the implementation of the measures was not assessed in the relevant studies. The kind of income loss is related to the limited agricultural activity. Additional costs: The additional cost that stem from the implementation of the measure is related to the log barriers and wood-made check dams as well as the jute geotextile application and the hydro-seeding technique. Other opportunity costs: Also the cost of the plants that were used for the afforestation of the area is included in the economic cost.
 Which link can be made to the ecosystem services approach? Hint: The actual benefits of improving nature's water storage capacity are essentially linked to an improved provision of some of the following ecosystem goods and services: Freshwater for drinking. Water provision to deliver water services to the economy both for drinking and non-drinking purposes. Water security (reliability of supply and resilience to drought). Health security (control of waterborne diseases). Flood security and protection. Storm surge protection. Biomass production. Amenities (associated to habitat protection): fish and plants, tourism, recreation, and others. Benefits of improved coastal water quality and ecological status for a sustainable commercial production of shellfish with human health and welfare values. 	The actual benefits of improving nature's water storage capacity are essentially linked to an improved provision of some of the following ecosystem goods and services: - Water provision to deliver water services to the economy both for drinking and non-drinking purposes. - Water security (reliability of supply and resilience to drought). - Flood security and protection. - Storm surge protection. - Amenities (associated to habitat protection): fish and plants, tourism, recreation, and others.

VII. Monitoring & maintenance requirements

Monitoring requirements	A permanent automatic meteorological monitoring station is necessary to be installed, in order to predict of the progress of the wildfire risk in the area as well as to inform the public in real time for the plant development.
Maintenance requirements	The maintenance requirements include the plants irrigation, clearing and pruning as well as bio-fertilizer application. The intensity and the frequency of the maintenance activities are related to the season the plant and the meteorological conditions in the specific area. The local authorities are responsible for the maintenance.
What are the administrative costs?	The expenses linked to maintenance are not assessed in the provided studies, however it is estimated that the responsible local authorities adequately cover them from their internal budgets. Additionally the cost for monitoring is considered relevantly affordable.

VIII. Performance metrics and assessment criteria

Which assessment methods and practices	The performance of the interventions was evaluated with	
are used for assessing the biophysical	the use of qualitative criteria on a scale of four grades	
impacts?	"excellent", "good", "moderate" and "poor".	
Which methods are used to assess costs,	The performance of the interventions was evaluated with	
benefits and cost-effectiveness of	the use of qualitative criteria on a scale of four grades	
measures?	"excellent", "good", "moderate" and "poor".	
	The evaluation of the installation of the timber structures	
	was excellent or good in a percentage of 70%.	
	The evaluation of hydro-seeding was excellent at a	
	percentage of 60%. For the geo-textile (jude) the	
	evaluation was good or moderate at a percentage of 60%,	
	due to the difficulty of the steep slopes.	
	As far as the vegetation interventions are concerned it is	
How cost-effective are NWRM's	estimated that the effectiveness was good or excellent at a	
compared to "traditional / structural"	percentage of 70%.	
measures?	The traditional /structural measures would include the	
	construction of reservoirs or water retaining installations	
	(e.g. small dams), as well as soil retention measures. These	
	interventions would apparently need more expensive	
	materials (e.g. concrete) and would have a greater impact	
	on the environment.	
	Thus the NWRM measures seem to be more cost-	
	effective compared to the traditional/structural measures.	
How do (if applicable) specific basin	As water is retained to the ground for longer period, water absorption	
characteristics influence the effectiveness	and infiltration were increased with a positive impact on the	
of measures?	groundwater and the aquifers of the specific basin.	
	The standard time delay for measuring the effects of measures are 1-2	
What is the standard time delay for	years as by then the natural environment has started to be restored.	
measuring the effects of the measures?	After 4-5 years the ecosystem is expected to be fully restored and the	
	retention is conducted naturally by the improved properties of the soil.	

IX. Main risks, implications, enabling factors and preconditions

What were the main implementation barriers?	Generally there were not significant delays in the implementation of the measures as the risks were associated with flood risk and landslides. The main implementation barriers were physical constraints such as the high slopes.	
What were the main enabling and success factors?	The main enabling and success factors was the positive attitude of decision makers, the willing stakeholders and the positive public perception and the existing expert knowledge and tools	
Financing	The main funding sources were donations by the Latsis J. Public Benefit Foundation as well as by EU-funds: Rural development funds (Agricultural Development Programme) The total expenses linked to the measure installation is 2.762.500 €.	
Flexibility & Adaptability	The current implementation is flexible and adaptable to changing baseline conditions as the log barriers can be easily removed when the vegetation is adequately restored. The cost to for adaptation is limited.	
Transferability	A similar application can be proposed, assessed and selected in respective wildfires that occur in steep hills that result in increased surface runoff. The necessary preconditions are the climate conditions and the soil properties and characteristics.	

X. <u>Lessons learned</u>

Key lessons	The measures are based on changing the morphology of the area as well as the soil composition. Thus, the length of the slopes was shortened, the surface roughness and the soil infiltration rates were increased, the surface runoff and
	sentiments were delayed and the soil humidity was increased.

XI. References

Source Type	Project Report	
Source Author(s)	Bourletsikas Athanasios	
Source Title	Post-fire water retention management: The case study of Ancient Olympia, Greece	
Year of publication	2014	
Editor/Publisher	-	
Source Weblink	-	
Key People	Name / affiliation 1. 2. 3. 4.	Contact details

Source Type	Other (specify)
-------------	-----------------

Source Author(s)	Lyrintzis Georgios	Lyrintzis Georgios	
Source Title	Restoration of the archeological an	Restoration of the archeological and the broader landscape of Olympia	
Year of publication	2011	2011	
Editor/Publisher	National Agricultural Research	National Agricultural Research Foundation (N.AG.RE.F)	
Source Weblink	www.nagref.gr/journals/publicat.	www.nagref.gr/journals/publications/arxaia_olympia.pdf	
Key People	Name / affiliation	Contact details	
	1.		
	2.		
	3.		
	4.		

XII. Photos Gallery



Picture 1: Kronios Hill after the implementation of the measures, Continuous Lines (Bourletsikas Athanasios, 2014)



Picture 2: Olympic Academy Hill after the implementation of the measures, Empty Space Lines, (Bourletsikas Athanasios, 2014)



Picture 3: Detail of the timber structures (26-11-2007) (Lyrintzis Georgios, 2011)